



UNDERGROUND SERVICE

NOTES:

1. CONSTRUCTION SHALL CONFORM TO THESE REQUIREMENTS EXCEPT AS OTHERWISE DIRECTED BY THE COUNTY ENGINEER.
2. CONTRACTOR SHALL INSTALL SERVICE CONDUIT INTO UTILITY COMPANY VAULT UNDER THE DIRECTION OF THE UTILITY COMPANY.
3. CONTRACTOR SHALL INSTALL #5 OR 5(T) PULL BOX, 2" SERVICE CONDUIT, AND 2" CONDUIT AND CONDUCTORS FROM EQUIPMENT TO PULL BOX.
4. CONDUIT AND CONDUCTOR TO ENTER PULL BOX THROUGH BOTTOM OF BOX. PULL BOXES SHALL BE PARALLEL WITH THE ROADWAY.
5. SEE COUNTY DRAWING NO. 600 NOT NO. 3 TO DETERMINE IF A #5 OR 5(T) PULL BOX IS REQUIRED. ALSO CHECK PLANS AND NOTES.

COUNTY OF SONOMA
DEPARTMENT OF TRANSPORTATION
AND PUBLIC WORKS

ELECTRIC SERVICE DETAIL
UNDERGROUND SERVICE

DATE: MAY 2004

REVISED:

APPROVED BY:

JH

SCALE:

NONE

DRAWING NO.

606